

SECTION



SECTION



SECTION

GEOTECHNICAL ENGINEER TO INSPECT ALL FOOTINGS AND CERTIFY FOUNDATION MATERIAL. INCREASE PAD DEPTH WITH 10MPa MASS CONCRETE IF NECESSARY TO:

1. OBTAIN AN ALLOWABLE BEARING PRESSURE OF 100 kPa. TO BE APPROVED BY THE GEOTECHNICAL ENGINEER.
2. HAVE A DISPERSION LINE OF 45° FROM UNDERSIDE OF PAD PASSING UNDER SERVICE PIPES.



GEOTECHNICAL ENGINEER TO INSPECT ALL FOOTINGS AND CERTIFY FOUNDATION MATERIAL. INCREASE PAD DEPTH WITH 10MPa MASS CONCRETE IF NECESSARY TO:

1. OBTAIN AN ALLOWABLE BEARING PRESSURE OF 100 kPa. TO BE APPROVED BY THE GEOTECHNICAL ENGINEER.
2. HAVE A DISPERSION LINE OF 45° FROM UNDERSIDE OF PAD PASSING UNDER SERVICE PIPES.

TYPICAL STRIP FOOTING DETAIL (SF#)



STRIP FOOTING (SF#) AND PAD FOOTING (PF#) JUNCTION

FIBRE STRIP FOOTING SCHEDULE			
FIBRE REINF TO BE DRAMIX 4D 65/60BG @25kg/m³			
MARK	'X' WIDTH	'Z' DEPTH	CONCRETE STRENGTH
SF1	1200	400	N32



PLAN

TYPICAL FIBRE PAD FOOTING DETAIL (PF#)
TYPICAL PORTAL COLUMN



PLAN

TYPICAL FIBRE PAD FOOTING DETAIL (PF#)
END WALL COLUMN



PLAN

TYPICAL FIBRE PAD FOOTING DETAIL (PF#)
SHS COLUMN

FIBRE PAD FOOTING SCHEDULE				
FIBRE REINF TO BE DRAMIX 4D 65/60BG @25kg/m³				
MARK	'Y' LENGTH	'X' WIDTH	'Z' DEPTH	CONCRETE STRENGTH
PF1	2400	3000	600	N32
PF2	2000	2400	600	N32
PF3	2200	2200	800	N32
PF4	1800	1800	400	N32
PF5	1400	1400	400	N32
PF6	600	600	400	N32



OPTION 1 – STOP & START FOOTING



OPTION 2 – LOCALLY THICKEN FOOTING

TYPICAL SERVICE PENETRATION TO FIBRE STRIP FOOTING DETAIL

DRN	AMENDMENTS	DATE	REV
NS	BAC APPROVAL	11.06.26	A

NORTHROP
PROJECT NUMBER: 250946

Drawn: HP	Checked:
Design Coordinated: HP	Compliance Checked: –
Authorised For Issue: NS	Construction Checked: –

SKYGATE PLAY

TYPICAL FOOTING DETAILS

BRISBANE AIRPORT CORPORATION PTY LTD
11 THE CIRCUIT, BRISBANE AIRPORT, QLD, 4008, AUSTRALIA
PO BOX 61, HAMILTON CENTRAL, QLD, 4007, AUSTRALIA
T: +61 7 3406 3000
E: INFO@BNE.COM.AU
W: BNE.COM.AU

Scale: 1 : 20
Size: A1
Revision: A

Drawing Number	Project No.	Originator	Volume	Level	Type	Discipline	Number
	25021 -	NOR -	XX -	01 -	DR -	ST -	001901

File Path: Autodesk Docs://250946 - BNE Play/25021-NOR-ZZ-ZZ-M3-ST-000001.rvt

Plot Date & Time: 11/06/2026 10:03:18 AM