SLAB NOTE:
PROVIDE GADJ AT ALL ROLLER DOORS AND GDJ'S TO ALL PEDESTRIAN DOORS TYPICAL

SLAB DESIGN IS BASED ON CBR 3%, MODULUS SUBGRADE REACTION 25kPa/mm

DENOTES DOWEL JOINT. ALLOW DANLEY 10MM DIAMOND DOWELS AT 450 CRS OR APPROVED EQUIVILENT

SLAB DESIGN ASSUMES A CLASS M REACTIVITY



SLAB PLAN

CONCRETE PAVEMENT LOADING SCHEDULE		
LEGEND	LOADING	PAVEMENT DESIGN
	AREA 51 SLAB 7.5kPa DISTRIBUTED LOAD (750kg/m2)	150mm CBR15 SUBBASE S40 CONCRETE 2 LAYERS PLASTIC 150 THICK TWINTEC AFT+09/60HE @ 23kg/m3 150 THICK DRAMIX 4D 80/60 BGE @ 20kg/m3 JOINT SEALANT TO BE DOWCORNING 888 OR SIMILAR
	GAME OVER SLAB 7.5kPa DISTRIBUTED LOAD (750kg/m2)	150mm CBR15 SUBBASE S40 CONCRETE 2 LAYERS PLASTIC 150 THICK TWINTEC AFT+09/60HE @ 23kg/m3 150 THICK DRAMIX 80/60 BGE @ 20kg/m3 JOINT SEALANT TO BE DOWCORNING 888 OR SIMILAR
	SERVICE DRIVEWAY AND CARPARK UNLIMTED REPETITIONS OF CARS AND VEHICLES NOT EXCEEDING 3500kg GROSS MASS	150mm CBR15 SUBBASE 150 THICK SLAB N32 CONCRETE SL82 TOP MESH DOWEL JOINTS MAX 25m CTRS SAWN JOINTS MAX 5m CTRS
	FOOTPATH 3kPa LIVE LOAD 1kPa SUPERIMPOSED DEAD LOAD	150mm CBR15 SUBBASE 120 THICK SLAB N32 CONCRETE SL82 TOP MESH DOWEL JOINTS MAX 25m CTRS SAWN JOINTS MAX 5m CTRS
	FIRE TANK 9.5M TALL TANK	150mm CBR15 SUBBASE 300 THICK SLAB N32 CONCRETE N16-200 EW btm + SL102 TOP



TYPICAL TRUCK HARDSTAND AND LIGHT DUTY PAVEMENT SAWN JOINT DETAIL – 'SJ1'

SCALE 1:10



TYPICAL FOOTPATH SAWN JOINT DETAIL – 'SJ2'

SCALE 1:10

- JOINT SUITABLE FOR PEDESTRIAN FOOTPATHS



TYPICAL TRUCK HARDSTAND AND LIGHT DUTY PAVEMENT DOWEL JOINT DETAIL – 'EDJ1'



TYPICAL FOOTPATH DOWEL JOINT DETAIL – 'EDJ2'

NOTE:

SETTLEMENT ANALYSIS OF TENNANT LOADING INDICATES GROUND IMPROVEMENT ISNT REQUIRED. IF THE BUILDING IS GOING TO BE BUILT WITH FUTURE FLEXIBILITY, CONSIDERATION TO FUTURE LOADING SCENARIOS SHOULD BE CONSIDERED TO CONFIRM GROUND IMPROVEMENT.

REACTIVITY:
THE SITE SHOULD BE PREPARED TO ACHEIVE A 'CLASS M' REACTIVITY. REFER TO DOUGLAS PARTNERS GEOTECHNICAL REPORT FOR DETAILS, WHICH INCLUDE THE REMOVAL OF UNCONTROLLED FILL AND A 700mm GRANULAR FILL CAPPING LAYER ACROSS THE SITE

Sheet size: A1

Drawing to be printed in colour

NOT FOR CONSTRUCTION

NORTHROP

BRISBANE
Level 25, 12 Creek Street
Brisbane City, QLD 4000
brisbane@northrop.com.au
(07) 3365 0400
ABN 81 094 433 100

PARTNERS

Brisbane Airport
Brisbane Airport Corporation Pty Ltd
11 The Circuit Brisbane Airport QLD 4008
PO Box 61 Hamilton QLD 4007 Australia
Telephone : 61 7 3406 3000
Fascimile : 61 7 3406 3111
Email : info@bne.com.au
www.brisbaneairport.com.au
ABN 54 076 870 650

Archipelago

DRAWN: Author | JOB MANAGER: Checker
DESIGNED: Designer | VERIFIER: Approver

1:100 0 5000

Scale at A1 — Refer to architect's drawings for setout

REV.	DESCRIPTION	ISSUED	DATE
A	FOR INFORMATION	NS	29/08/25
B	FOR INFORMATION	JS	21/11/25
C	FOR INFORMATION	NS	19/12/25
D	FOR TENDER	NS	04/02/26

PROJECT
BAC BNE SKYGATE PLAY

ADDRESS

DRAWING TITLE
SLAB PLAN

JOB No.
250946

DRAWING No.
25021-NRP-XX-01-DR-ST-00000
4

REV.
D