NOTE: ALL CIVIL ENGINEERING CONSTRUCTION WORKS TO BE CARRIED OUT IN ACCORDANCE WITH AUTHORITY (INCLUDING LGA AND WATER AUTHORITY) STANDARDS AND GUIDELINES.THE AFOREMENTIONED GUIDELINES INCLUSIVE OF ALL SPECIFICATIONS TAKE PRECEDENCE OVER NOTES PROVIDED BELOW.

PAVEMENT JOINTS

1. PROVIDE 10mm ABLEFLEX BETWEEN NEW CONCRETE WORKS AND EXISTING STRUCTURES.

2. LOCAL AUTHORITY REQUIREMENTS SHALL TAKE PRECEDENCE WITHIN THE PUBLIC ROAD RESERVE.

3. DOWELS TO BE PLACED ON PROPRIETARY CRADLES TO ENSURE CORRECT SPACING AND ALIGNMENT.

4. PEDESTRIAN PAVEMENTS

ALL PEDESTRIAN PAVEMENTS ARE TO BE JOINTED AS FOLLOWS U.N.O. ON THE DESIGN DRAWINGS.

4.1 EXPANSION JOINTS ARE TO BE LOCATED WHERE POSSIBLE AT TANGENT POINTS OF CURVES AND ELSEWHERE AT MAX. 12.0m CENTRES.

4.2 WEAKENED PLANE JOINTS (SAWN OR TOOL JOINTS) ARE TO BE LOCATED AT A MAX. SPACING OF 1.5m x WIDTH OF THE PAVEMENT.

4.3 WHERE POSSIBLE JOINTS SHOULD BE LOCATED TO MATCH KERBING AND OR ADJACENT PAVEMENT JOINTS.

4.4 TYPICAL PEDESTRIAN PAVEMENT JOINT DETAIL



5. VEHICULAR PAVEMENTS

ALL VEHICULAR PAVEMENTS TO BE JOINTED AS FOLLOWS U.N.O. ON THE DESIGN DRAWINGS.

5.1 TIED KEYED CONSTRUCTION JOINTS SHOULD GENERALLY BE LOCATED LONGITUDINALLY AT A MAX. OF 6.0m CENTRES.

5.2 SAWN JOINTS SHOULD GENERALLY BE LOCATED LATERALLY AT A MAX. OF 6.0m CENTRES WITH DOWELED EXPANSION JOINTS AT MAX. 18.0m CENTRES.

5.3 TYPICAL VEHICULAR PAVEMENT JOINT DETAIL.



6. KERB EXPANSION JOINTS SHALL BE FORMED FROM 10mm ABLEFLEX FOR FULL DEPTH OF SECTION.

7. KERB EXPANSION JOINTS TO BE LOCATED AT DRAINAGE PITS, TANGENT POINTS OF CURVES / CORNERS AND AT 12m MAX CENTRES.

8. KERB TOOLED JOINTS TO BE MIN 3mm WIDE AND LOCATED AT MAX 3m CENTRES.

9. INTEGRAL KERB JOINTS SHALL MATCH THE LOCATION OF PAVEMENT JOINTS.

LANDSCAPING

1. REFER TO DRAWINGS BY OTHERS FOR DETAILS OF PROPOSED LANDSCAPING TREATMENT.

2. U.N.O ALL DISTURBED SURFACES ARE TO BE TEMPORARILY STABILISED WITH HYDROMULCH UPON COMPLETION OF WORKS.

3. A 500mm STRIP OF TURF (CT2 COUCH) IS TO BE PLACED BEHIND ALL NEW KERB AND GUTTER / ROLL KERB.

CONCRETE

1. CARRY OUT ALL CONCRETE WORK IN ACCORDANCE WITH AS3600 AND NATSPEC CONCRETE STANDARDS.

2. CONCRETE PROPERTIES AND COVER TO REINFORCING:

ELEMENT	CONCRETE STRENGTH f'c (MPa)	MAX. 56 DAY DRYING SHRINKAGE	COVER (mm)	
SLABS ON GROUND	32	650microns	TOP 40	BTM 40
TANK LID	40	700microns	TOP 40	BTM 40

MAXIMUM AGGREGATE SIZE = 20mm U.N.O.
SLUMP DURING PLACING = 75mm
EXPOSURE CLASSIFICATION = B1

NO ADMIXTURES SHALL BE USED IN CONCRETE MIX UNLESS APPROVED BY STRUCTURAL ENGINEER IN WRITING.

3. CONCRETE PROPERTIES FOR SLABS AND BEAMS SHALL BE VARIED FROM NORMAL CLASS AS FOLLOWS:
   - MINIMUM CEMENT CONTENT 250kg/cu.m.
   - PRIOR TO COMMENCEMENT CONCRETE SUPPLIER TO PROVIDE DRYING SHRINKAGE TEST

RESULTS FROM PRODUCTION ASSESSMENT AS EVIDENCE THAT SPECIFIED DRYING SHRINKAGE LIMITS CAN BE ACHIEVED USING NORMAL MIX DESIGN.

4. SUBMIT FOR APPROVAL THE FOLLOWING TO THE STRUCTURAL ENGINEER:
   - CURING PROCEDURE (PVA MEMBRANES NOT PERMITTED)
   - STRIPPING PROCEDURE
   - DETAILS AND LOCATION OF CAST IN SERVICES
   - CONDUITS, PENETRATIONS AND CONSTRUCTION JOINT LOCATIONS

5. ALL CONCRETE MIXES SHALL BE DESIGNED BY A RECOGNISED TESTING LAB AND SUBMITTED FOR REVIEW BY THE STRUCTURAL ENGINEER.

6. ALL COMPRESSIVE STRENGTH TEST REPORTS SHALL BE SUBMITTED TO THE STRUCTURAL ENGINEER FOR REVIEW.

7. PROJECT CONTROL TESTING SHALL BE CARRIED OUT ON ALL CONCRETE IN ACCORDANCE WITH AS1379. TEST CYLINDERS ARE TO BE KEPT ON SITE.

8. ALL CONCRETE IS TO BE CONTINUOUSLY CURED FOR A MINIMUM PERIOD OF 10 DAYS AFTER PLACING. CURING TO COMMENCE IMMEDIATELY AFTER FINISHING. SPRAY ON CURING COMPOUNDS TO COMPLY WITH AS3799.

9. FOR TENDER PURPOSES ASSUME MINIMUM STRIPPING TIMES AND EXTENT OF BACK PROPPING AS PER AS3610-1995 SECTION 5.0 AND AS PER GENERAL NOTES FOR FORMWORK AND PROPPING.

10. FORMWORK FINISH CLASSIFICATION TO AS3600:

ELEMENT	CLASS
- INGROUND FOOTINGS	5
- RETAINING WALLS	5 EARTH FACE
- RETAINING WALLS	3 EXPOSED FACE
- COLUMNS	2
- BEAMS AND SLABS	2

11. SURFACE FINISHES:
   - COLUMNS AND WALLS OFF FORM

12. COMPACT ALL CONCRETE INCLUDING FOOTINGS AND SLABS, USING MECHANICAL VIBRATORS.

13. PLACE CONCRETE CONTINUOUSLY BETWEEN CONSTRUCTION JOINTS SHOWN ON PLAN. DO NOT BREAK OR INTERRUPT SUCCESSIVE POURS SUCH THAT COLD JOINTS OCCUR. ANY REVISIONS OR ADDITIONS TO CONSTRUCTION JOINTS SHOWN ON PLAN REQUIRE APPROVAL FROM THE STRUCTURAL ENGINEER.

14. CONCRETE PROFILES:
   - BEAM DEPTHS ARE WRITTEN FIRST AND INCLUDE THE SLAB THICKNESS.
   - SIZES OF CONCRETE ELEMENTS DO NOT INCLUDE THICKNESS OF APPLIED FINISHES.
   - NO HOLES, CHASES OR EMBEDMENT OF PIPES OTHER THAN SHOWN IN THE STRUCTURAL DRAWINGS SHALL BE MADE IN CONCRETE MEMBERS WITHOUT THE PRIOR WRITTEN APPROVAL OF THE STRUCTURAL ENGINEER.
   - PROVIDE DRIP GROOVES AT ALL EXPOSED EDGES, CHAMFERS, DRIP GROOVES, REGLETS ETC TO BE TO ARCHITECTS DETAILS.

15. ALL PENETRATIONS TO HAVE 2-N16 TRIMMER BARS TOP AND BOTTOM TO EACH FACE U.N.O. EXTEND TRIMMERS 600 BEYOND PENETRATION.

16. SETDOWNS OR FALLS IN FLOOR SURFACES ARE NOT PERMITTED UNLESS SHOWN ON DRAWINGS. MAINTAIN MINIMUM SLAB THICKNESS SHOWN ON PLAN WHERE FALLS OCCUR.

17. REINFORCEMENT GRADE AND NOTATION:

SYMBOL	BAR SHAPE	STRENGTH GRADE (MPa)	DUCTILITY CLASS	TO COMPLY WITH AUST. STANDARD
N	DEFORMED RIB BAR	500	NORMAL	AS4671
R	PLAIN ROUND BAR	250	NORMAL	AS4671
RL	RECTANGULAR MESH OF DEFORMED RIB BAR	500	LOW	AS4671
SL	SQUARE MESH OF DEFORMED RIB BAR	500	LOW	AS4671
L-TM	TRENCH MESH	500	LOW	AS4671

ALL REINFORCING BARS SHALL BE GRADE D500N TO AS4671 AND ALL MESH SHALL BE GRADE 500L TO AS4671 U.N.O. CLASS L REINFORCEMENT SHALL NOT BE USED U.N.O.

REINFORCEMENT LABELS:



18. REINFORCEMENT IS REPRESENTED DIAGRAMMATICALLY, AND NOT NECESSARILY IN TRUE PROJECTION. BARS SHOWN ARE INDICATIVE ONLY AND LENGTHS MAY VARY. BEAM ELEVATIONS TAKE PRECEDENCE OVER SECTIONS. SLAB PLANS TAKE PRECEDENCE OVER SECTIONS. REFER TO SECTIONS FOR EXTRA BARS THAT MAY BE REQUIRED.

19. USE ONLY ALL PLASTIC OR CONCRETE CHAIRS AT EXTERNAL SURFACES.

20. SITE BENDING OF REINFORCEMENT BARS SHALL BE DONE WITHOUT HEATING USING A RE-BENDING TOOL. THE BARS SHALL BE RE-BENT AGAINST A FLAT SURFACE OR A PIN WITH A DIAMETER NOT LESS THAN THE MINIMUM PIN SIZE PRESCRIBED IN AS3600-2001.

21. SPLICES IN REINFORCEMENT SHALL BE MADE ONLY IN POSITIONS SHOWN ON THE STRUCTURAL DRAWINGS OR IN POSITIONS OTHERWISE APPROVED IN WRITING BY THE STRUCTURAL ENGINEER. LAPS SHALL BE IN ACCORDANCE WITH AS3600 SECTION 13 AND NOT LESS THAN THE DEVELOPMENT LENGTH FOR EACH BAR.

22. FOR LAPS IN MESH REFER TO SLAB ON GROUND NOTES.

23. WELDING OF REINFORCEMENT SHALL NOT BE PERMITTED UNLESS SHOWN ON THE STRUCTURAL DRAWINGS OR APPROVED BY THE STRUCTURAL ENGINEER

24. AT EXTERNALLY EXPOSED SURFACES NO METALLIC ITEMS INCLUDING FORM BOLTS, FORM SPACERS, METALLIC BAR CHAIRS AND TIE WIRE ARE TO BE PLACED IN THE COVER ZONE.

25. ALL REINFORCEMENT, ANCHOR BOLTS AND OTHER CONCRETE INSERTS SHALL BE WELL SECURED IN POSITION AND INSPECTED BY THE STRUCTURAL ENGINEER PRIOR TO PLACING CONCRETE.

26. HOLD DOWN BOLTS SHALL BE HOT DIPPED GALVANISED.

27. U.N.O, ALL MASONRY ANCHORS INTO CONCRETE SHALL BE RAMSET TRUBOLTS (LONGEST VERSION) OR APPROVED EQUIVALENT. BOLTS SHALL BE GALVANISED WHERE THEY ARE ADJOINING NON FERROUS OR PREPAINTED MEMBERS. PROVIDE STAINLESS STEEL BOLTS FOR ALL EXTERNAL CONDITIONS, OR WHERE EXPOSED TO THE WEATHER.

SCOUR PROTECTION ROCK

1. ROCK USED IN THE SCOUR PROTECTION SHALL CONSIST OF MATERIAL WHICH COMPLIES WITH THESE NOTES AND THE DRAWINGS. THIS REQUIREMENT APPLIES TO BOTH IMPORTED ROCK AND IN-SITU ROCK WHICH IS RE-USED.

2. INDIVIDUAL ROCKS SHALL BE FREE FROM CRACKS, CLEAVAGE PLANES, SEAMS AND DEFECTS WHICH WOULD RESULT IN THE BREAKDOWN OF THE ROCK IN SERVICE.

3. ROCK UNITS SHALL BE EITHER SEDIMENTARY RACK ONLY OR IGNEOUS ROCK ONLY AND AS A MINIMUM, SHALL SATISFY THE FOLLOWING CRITERIA:

   - ROCK SHALL BE ROUGH AND ANGULAR.
   - ROCK SHALL HAVE A MINIMUM DRY DENSITY OF 2200 kg/m.
   - IGNEOUS ROCK SHALL HAVE NO MORE THAN 10% (BY VOLUME) OLIVINE MATERIAL AND SHALL EXHIBIT NO ZONES OF SECONDARY ALTERATION SUCH AS CHLORITISATION. SEDIMENTARY ROCK SHALL HAVE A MINIMUM SODIUM SULPHATE SOUNDNESS WEIGHT LOSS NOT EXCEEDING 25%.
   - ROCK SHALL HAVE A SATURATED POINT LOAD STRENGTH INDEX (IS50) NO LESS THAN 5.0 MPa FOR IGNEOUS ROCK AND 1.5 MPa FOR SEDIMENTARY ROCK.
   - THE RATIO OF THE MAXIMUM DIMENSION TO THE MINIMUM DIMENSION, MEASURED AT RIGHT ANGLES TO THE MAXIMUM DIMENSION SHALL NOT EXCEED 2.5.

4. THE ROCK UNITS SHALL BE PLACED SUCH THAT THE SPECIFIED REQUIREMENTS FOR SIZE, FINISHED SIDE SLOPES, TOP AND TOE LEVELS AND DENSITY REQUIREMENTS, ARE SATISFIED. IN ADDITION, ROCKS SHALL BE WEDGED AND LOCKED TOGETHER SUCH THAT THEY ARE NOT FREE TO MOVE. ROCK UNITS SHALL NOT BE ROLLED OR DROPPED INTO POSITION, THEY SHALL BE PLACED.

5. THE METHOD OF ROCK PLACEMENT SHALL BE SUCH AS TO MINIMISE ITS BREAKDOWN ON HANDLING AND THE PRODUCTION OF FINES.

6. A NON-WOVEN GEOTEXTILE (BIDIM A64 OR EQUIVALENT) SHALL BE PLACED UNDERNEATH AND BEHIND ALL ROCK ARMOUR AND EXTEND 0.5m ABOVE THE EXTENT OF THE WORKS OR AS OTHERWISE SHOWN ON THE DRAWINGS. THE GEOTEXTILE IS TO BE LAID ON A NEATLY TRIMMED BATTER THAT IS FREE OF HOLLOWS OR SHARP OBJECTS.

7. GEOTEXTILE LAYERS SHALL EITHER OVERLAP ON ANOTHER BY 1000mm OR BE SEWN TOGETHER (WITH A NON-BIODEGRADABLE THREAD) WITH AN OVERLAP OF 100mm.

8. ROCK SUB-ARMOUR SHALL BE PLACED UPON THE GEOTEXTILE IN A LAYER NO LESS THAN 150mm THICK UNLESS NOTED OTHERWISE ON DRAWINGS.

9. ROCK ARMOUR SHALL BE SELECTIVELY HAND PLACED UPON THE SUB-ARMOUR TO ENSURE A SNUG FIT SUCH THAT INDIVIDUAL ROCKS ARE NOT TO MOVE. THE PLACING OF ANY ARMOUR ROCK SHALL BE COMPLETED IN SUCH A MANNER TO MINIMISE THE DISTURBANCE OR DISLODGEMENT OF THE SUB-ARMOUR.

10. THE ROCK ARMOUR SHALL BE NO LESS THAN 375mm THICK UNLESS NOTED OTHERWISE ON THE DRAWINGS.

11. THE ARMOUR ROCK AND SUB-ARMOUR ROCK SHALL BE PLACED TO THE CONSTRUCTION TOLERANCES SHOWN ON THE DRAWINGS.

12. AT LEAST FOURTEEN (14) DAYS PRIOR TO THE SUPPLY OF ANY ROCK, THE CONTRACTOR SHALL PROVIDE DOCUMENTATION TO DEMONSTRATE THAT THE ROCK TO BE SUPPLIED COMPLIES WITH THE REQUIREMENTS OF THE SPECIFICATION.

3D INFORMATION DISCLAIMER

PLEASE BE ADVISED 12D DESIGN FILE, IF SUPPLIED, IS DEEMED TO BE AN ACCURATE REFLECTION OF NORTHROP'S DESIGN AT THE TIME OF FINAL DESIGN DEVELOPMENT AND MAY NOT FULLY REFLECT THE DESIGN SURFACE AS PRESENTED. HOWEVER THIS INFORMATION SHALL BE VERIFIED BY THE CONTRACTOR PRIOR TO INCORPORATION IN THE CONSTRUCTION WORKS.

YOU ARE FURTHER ADVISED THAT ISSUED HARDCOPY/PDF PLANS AND DOCUMENTS TAKE PRECEDENCE OVER THE SUPPLIED ELECTRONIC INFORMATION AND ANY INCONSTANCIES SHOULD IMMEDIATELY BE REPORTED TO NORTHROP CONSULTING ENGINEERS FOR VERIFICATION PRIOR TO THEIR INCORPORATION IN THE WORKS.

NORTHROP CONSULTING ENGINEERS TAKES NO RESPONSIBILITY FOR USE OF NON-VERIFIED 3D DESIGN INFORMATION USED IN THE WORKS.

THE USE OF THE 3D MODEL INFORMATION SHALL CONSTITUTE ACKNOWLEDGMENT AND ACCEPTANCE OF THE ABOVE STATEMENTS BY THE RECIPIENT.

RETAINING

1. ALL RETAINING WALL/TERRACING TO SATISFY AUTHORITY CODES & STANDARDS. REFER TO COUNCIL'S FILLING AND EXCAVATION/EARTHWORKS CODES FOR FURTHER DETAILS. RETAINING WALL FINISHES THAT PRESENT TO ADJOINING LAND ARE TO BE OF QUALITY APPEARANCE, HAVE LOW MAINTENANCE REQUIREMENTS AND BE COMPATIBLE WITH SURROUNDING DEVELOPMENT.

2. ANY PROPOSED RETAINING WALL WORKS (INCLUDING REAR OF RETAINING WALL DRAINAGE INFRASTRUCTURE) MUST BE WHOLLY WITHIN THE PROPERTY BOUNDARY OF THE SUBJECT SITE.

3. ALL RETAINING WALLS SHOWN ON NORTHROP DRAWINGS ARE INDICATIVE ONLY WITH FINAL RETAINING WALL STRUCTURAL DESIGN & CONSTRUCTION CERTIFICATE BY MANUFACTURER / INSTALLER OR BY RPEQ STRUCTURAL ENGINEER.

4. CONTRACTOR TO CONFIRM RETAINING WALL BACKSLOPE ANGLE (IF STEEPER THAN 1in4) WITH GEOTECHNICAL ENGINEER PRIOR TO CONSTRUCTION.

5. CONTRACTOR TO ENSURE FREE DRAINING (NO FINES) BACKFILL MATERIAL IS IMPLEMENTED BEHIND ALL RETAINING WALL U.N.O BY RPEQ STRUCTURAL ENGINEER. SOCKED SUBSOIL DRAINAGE (SLOTTED PIPE) TO BE PLACED BEHIND BASE OF RETAINING WALL AND IS TO DISCHARGE TO SUITABLE POINT OF DISCHARGE, OR ALLOW FOR WEEP HOLES AT BASE OF WALL.

6. ENSURE NO VEHICLE LOADING WITHIN A HORIZONTAL DISTANCE FROM TOP OF WALL EQUAL TO THE HEIGHT OF THE WALL DURING OR AFTER CONSTRUCTION, U.N.O BY RPEQ ENGINEERED DESIGN WHICH ALLOWS FOR LOADING.

NOT FOR CONSTRUCTION

NOT TO SCALE

COPYRIGHT :
REPRODUCTION OF WHOLE OR PART OF THIS DOCUMENT CONSTITUTES AN INFRINGEMENT OF COPYRIGHT. THE INFORMATION, IDEAS AND CONCEPTS CONTAINED IN THIS DOCUMENT ARE CONFIDENTIAL. THE RECIPIENT(S) OF THIS DOCUMENT IS PROHIBITED FROM DISCLOSING SUCH INFORMATION IDEAS AND CONCEPTS TO ANY PERSON WITHOUT THE PRIOR WRITTEN CONSENT OF THE BRISBANE AIRPORT CORPORATION PTY. LTD.

DRN	AMENDMENTS	DATE	REV
JD	PRELIMINARY DESIGN 30%	12.09.25	A
JD	ISSUED FOR TENDER	23.12.25	B
JD	ISSUED FOR TENDER	28.01.26	C
LQ	ISSUED FOR TENDER	30.01.26	D
MM	ISSUED FOR APPROVAL	11.06.26	E

XENIA

NORTHROP
Brisbane
The Annex, Level 8, 12 Creek Street, Brisbane QLD 4000
GPO BOX 423 Brisbane QLD 4001
(07) 3365 0400 brisbane@northrop.com.au
ABN 81 094 433 100

Drawn M.MANLAPIT 11.06.26	Checked A.TATHAM 11.06.26
Design Coordinated R.MITCHELL 11.06.26	Compliance Checked S.KILLORAN 11.06.26
Authorised For Issue S.KILLORAN 11.06.26	Construction Checked N/A

SKYGATE PLAY
BRISBANE AIRPORT

CIVIL SPECIFICATION NOTES
SHEET 3 OF 3

Brisbane Airport
BRISBANE AIRPORT CORPORATION PTY LTD
11 THE CIRCUIT, BRISBANE AIRPORT QLD 4008
PO BOX 61, HAMILTON CENTRAL QLD 4007 AUSTRALIA
T +61734063000
E INFO@BNE.COM.AU
W BNE.COM.AU

Scale: AS ABOVE
Size: A1
Revision: E

Drawing Number	Project No.	Originator	Volume	Level	Type	Discipline	Number
	25021	NRP	XX	XX	DR	CI	000012

File: 250946-C-000010-Spec.dwg
C:\12dS\data\NorthropSYN\250946 - BNE PLAY Skygate_572\CAD\4-DD
Pentable: ----
Printer: AUTOCAD PDF (GENERAL DOCUMENTATION)
User: Mark Manlapit
Plot Date & Time: 6/11/2026 7:15:24 AM