




- LOADING NOTES**
- REFER S0.001-S0.003 FOR CONSTRUCTION NOTES
 - THE STRUCTURE HAS BEEN DESIGNED FOR THE LOADS NOMINATED ON THIS DRAWING.
 - LOADS HAVE BEEN APPLIED IN ACCORDANCE WITH 1170.1 USING SAFETY FACTORS AND PROBABILITY LOADING EVENTS.
 - LOADING IN EXCESS OF PROBABILITY LOADING EVENT WILL RESULT IN DAMAGE TO STRUCTURE REQUIRING MAINTENANCE OR REPAIR.
 - THE HYDRAULIC ENGINEER IS RESPONSIBLE FOR RESOLVING ALL HYDRAULIC THRUSTING FORCES FROM PUMPS AND PIPE WORK. ANY FORCES BEING IMPOSED ON OR NEAR THE STRUCTURE THE HYDRAULIC ENGINEER MUST PROVIDE LOADING DETAILS.
 - INTERNAL WIND PRESSURE CO-EFFICIENT (Cpi)
WAREHOUSE +0.2 -0.3
OFFICE +0.2 -0.3
 - ALL DOORS AND WINDOWS SHALL BE DESIGNED, MANUFACTURED AND INSTALLED TO RESIST THE FOLLOWING WIND PRESSURES:
INWARDS WIND PRESSURE: 125 kPa
OUTWARDS WIND PRESSURE: 106 kPa
 - LOCAL PRESSURE CO-EFFICIENTS HAVE NOT BEEN APPLIED TO THE ABOVE LOADING. REFER AS1170.2

- GROUND LOADING LEGEND**
- 1** **AREA 51**
7.5kPa DISTRIBUTED LOAD (750kg/m²)
 - 2** **GAME OVER**
7.5kPa DISTRIBUTED LOAD (750kg/m²)
 - 3** **DRIVEWAY AND CARPARK**
UNLIMITED REPETITIONS OF CARS AND VEHICLES NOT EXCEEDING 3500kg GROSS MASS
 - 4** **FOOTPATH**
LIVE LOAD: 3kPa
SUPERIMPOSED DEAD LOAD: 1kPa
 - 5** **FIRE TANK**
LIVE LOAD: 5kPa
SUPERIMPOSED DEAD LOAD: 60kPa
 - 6** **BUILDING SERVICE**
LIVE LOAD: 5kPa
SUPERIMPOSED DEAD LOAD: 1kPa
 - 7** **TRANSFORMER**
LIVE LOAD: 5kPa
SUPERIMPOSED DEAD LOAD: 1kPa

- ROOF LOADING LEGEND**
- 10** **SNOW WORLD**
LIVE LOAD: 0.25kPa
SUPERIMPOSED DEAD LOAD: 0.5kPa
PLANT: TO BE CONFIRMED
SOLAR: 0.15kPa
HAIL: 0.32kPa
 - 11** **AREA 51**
LIVE LOAD: 0.25kPa
SUPERIMPOSED DEAD LOAD: 0.2kPa
PLANT: TO BE CONFIRMED
SOLAR: 0.15kPa
HAIL: 0.32kPa
 - 12** **GAMEOVER**
LIVE LOAD: 0.25kPa
SUPERIMPOSED DEAD LOAD: 0.15kPa
PLANT: TO BE CONFIRMED
SOLAR: 0.15kPa
HAIL: 0.32kPa
 - 13** **AWNING**
LIVE LOAD: 0.25kPa
SUPERIMPOSED DEAD LOAD: 0.15kPa