

Skygate Play – Separable Portions (SPs)

1. Separable Portion 1 (SP1) – Area 51 Tenancy

- a) Refer to attached Site plan showing physical extent of SP1 Works.
- b) All work under the Contract necessary to obtain an interim Certificate of Compliance for all SP1 Works (interim CoC).
- c) Completion of all design work required to undertake and complete the Works in order to obtain the interim CoC for SP1 Works and enable the Tenant to commence its lease in accordance with its AtL.
- d) Obtain all Airport Building Controller (ABC) Building Approvals (BAs) required to undertake and complete the Works forming SP1.
- e) Obtain any required Authority Approvals to complete the SP1 Works. These may include Energex, Urban Utilities (UU), Brisbane City Council (BCC) and Aviation Rescue Fire Fighting (ARFF).
- f) Complete any external authority connections, relocations, protection or modifications as required in any Authority Approvals obtained and as required to complete the SP 1 Works.
- g) Undertake infrastructure upgrades as required to obtain the interim CoC for the SP1 Works. These include new HV/LV Pad Mount transformer, Fire Sprinkler tanks, Hydrant Ring Main, Fire Booster Assembly, Stormwater swales and in ground infrastructure.
- h) Complete all structural installations required to obtain the interim CoC for the SP1 Works. These may include in ground piling and footings, slabs, external paving and roads (specifically services road), steel framing, roof, and wall structures.
- i) Complete Civil works required to obtain the interim CoC for the SP1 Works including but not limited to bulk and detailed earthworks, road construction (Service road and carpark), parking, swales, loading docks, stormwater reticulation, drainage, fill import and removal, site remediation, landscaping and bund installation.
- j) Complete all services installations required to obtain the interim CoC for the SP1 Works. These may include Mechanical, Heating Ventilation Air Conditioning (HVAC), Wet and Dry Fire, Emergency Lighting, Electrical (HV & LV), Lighting, Comms, Security (Access Controls and CCTV), Hydraulic.
- k) Complete all external works including but not limited to landscaping, lighting, access controls, paving, roads, line marking, signage and outdoor furniture required to obtain the interim CoC.
- l) Complete all signage including but not limited to statutory, wayfinding and tenancy signage required to obtain the interim CoC for SP1.
- m) Undertake final commissioning including BAC Witness Commissioning, User Acceptance Training (UAT) and any external Authority Witness commissioning that may be required. Final commissioning and testing is to be undertaken and programmed so as to minimise interruptions to the Tenant of SP1. If required, commissioning may need to be completed out of regular working hours.
- n) Provision of As Builts, User Manuals, warranties, design and installation certificates and commissioning results for the SP1 Works as per Contract requirements and to enable the safe use, operation and maintenance of the works.

- o) Defects Liability Period (DLP) and maintenance services for SP1 Works.

2. Separable Portion 2 (SP2) – ‘Game Over’ Tenancy and External Works and all other WUC not forming part of any other Separable Portion

- a) Refer to attached Site plan showing extents of SP2.
- b) Obtain a Final Certificate of Compliance for all of the Works (including the Works forming Separable Portion 1).
- c) Relocation of all site amenities, laydown areas, staff and contractor parking, hoardings, fencing, cranes, plant, construction signage and equipment so as not to disrupt the ongoing operations of SP1 in any way.
- d) After SP1 has achieved Practical Completion, maintain all access to the SP1 Works and surrounding amenities including paving, carpark, landscaping, fire egress, plantrooms, and roads.
- e) Minimise all construction noise, vibration, and dust generation.
- f) Completion of all design work required to undertake and complete the works required to obtain CoC for the SP2 Works and enable the Tenant to commence its lease in accordance with its AtL.
- g) Obtain all Airport Building Controller (ABC) Building Approvals (BAs) required to undertake and complete the works identified in this SP2.
- h) Obtain any required Authority Approvals to complete the works. These may include Energex, Urban Utilities (UU), Brisbane City Council (BCC), Aviation Rescue Fire Fighting (ARFF).
- i) Complete any external authority connections, relocations, protection or modifications as required in any Authority Approvals obtained and as required to complete the SP 2 Works.
- j) Undertake infrastructure upgrades as required to obtain the SP2 interim CoC. These may include but not be limited to; new HV/LV transformer, Fire Sprinkler tanks, Hydrant Ring main, Stormwater swales and in ground infrastructure.
- k) Complete all structural installations required to obtain the SP2 interim CoC. These may include in ground piling and footings, slabs, external paving and roads, steel framing, roof, and wall structures including cladding and glazing).
- l) Complete all services installations required to obtain the interim SP2 CoC. These may include Mechanical (including Kitchen Exhaust), Heating Ventilation Air Conditioning (HVAC), Wet and Dry Fire, Electrical (HV & LV), Lighting, Comms, Security (Access and CCTV), Hydraulic.
- m) Complete all external works including but not limited to landscaping, lighting, access controls, wayfinding signage, statutory signage, paving, roads, line marking, signage, outdoor furniture required to obtain an interim CoC.
- n) Undertake final commissioning including BAC Witness Commissioning, User Acceptance Training (UAT) and any external Authority Witness Commissioning that may be required. Final commissioning and testing is to be undertaken and programmed so as to minimise interruptions to the tenants of SP1 (Area 51). If required, commissioning may need to be completed out of regular working hours.



- o) Provision of As Builts, User Manuals, warranties, design and installation certificates and commissioning results for the SP2 Works as per Contract requirements and to enable the safe use, operation and maintenance of the works.
- p) Defects Liability Period (DLP) and maintenance services for SP2 Works.
- q) All other work under the Contract not included in any other Separable Portion.